



PTH 300-500



TRACK LAYING TELESCOPIC GANTRIES

- Lay or renew up to 450 m of track per hour
- One pair lifts 18 to 30 tons
- The travelling beam can move the load laterally and handles the sleepers with chains or hydraulic clamps
- Up to 36 m panels or 70 sleepers, wooden or concrete, can be handled
- 4 wheels hydrostatically driven on auxiliary runway to suit 1 000 to 1 676 mm track gauges; up to 16 kmph on flat under load
- Synchronised travelling control
- 75 to 120 HP
- Gantries and beam are easily transported on standard flat wagons in most gauges



ТЕЛЕСКОПИЧЕСКИЕ ПОРТАЛЬНЫЕ ПУТЕУКЛАДЧИКИ

- Укладка или замена до 450 м пути в час
- Грузоподъемность пары: от 18 до 30 т
- Шпалоподъемная балка с цепями или гидравлическими захватами имеет встроенное устройство для рихтовки груза
- Подъем рельсошпальной решетки длиной до 36 м или до 70 деревянных или железобетонных шпал
- Гидростатическая трансмиссия с приводом на 4 колеса для движения по временному пути с шириной колеи от 1000 до 1676 мм; скорость до 16 км/ч (с грузом, без уклона)
- Синхронизированное управление
- Мощность от 75 до 120 л.с.
- Перевозка на стандартных вагонах-платформах, без нарушения габарита

We reserve the right to make any alteration or improvement deemed necessary to this equipment. Illustrations may include optional equipment.

Мы оставляем за собой право вносить изменения в характеристики оборудования. Иллюстрации могут включать оборудование, поставляемое за дополнительную плату.